

**GOVERNMENT OF TELANGANA
ABSTRACT**

NREGS – Telangana and Other developmental schemes – Revision of Rural Standard Schedule of Rates (RSSR 2014-15) – Orders – Issued.

PANCHAYAT RAJ & RURAL DEVELOPMENT (RD.I) DEPARTMENT

G.O.Ms.No. 3

Dated:23-07-2014

Read the following:

1. G.O.Ms.No.107, PR&RD (RD.II) Dept., GoAP, Dated:20-03-2013.
2. GOI Lr No.J-11011/1/2009- MGNREGA(Pt.III), Dated:13-02-2014.

<>>

ORDER:

Government of India vide reference Second read above has notified the wage rate for unskilled manual work taken up under MGNREGS as Rs.169/-.

2. Para 7 of MGNREG Act states that when wages are directly linked with the quantity of work, the wages shall be paid according to the schedule of rates fixed by the State Government for different types of work every year, in consultation with the State Council.

3. In order to ensure the revised wage rate to the unskilled wage seekers the task rates issued in the reference first read above are superceded and the Government orders for revision of the tasks rates (RSSR 2014-15) as annexed to the orders. The increased rates shall be come into force with immediate effect.

4. The RSSR 2014-15 is prepared in comprehensive with different categories of works taken up under MGNREGS.

5. The copy of the GO is available on website goir.Telangana.gov.in

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF TELANGANA)

J.RAYMOND PETER
PRINCIPAL SECRETARY TO GOVERNMENT

To

The Commissioner, Rural Development, Telangana, Hyderabad
The Director (EGS) O/o the Commissioner (RD), Telangana, Hyderabad
All the District Collectors and District Programme Coordinators, NREGS
All the Project Directors, DWMA & Addl. District Programme Coordinators, NREGS
All the Project Directors, DRDAs and Additional District Programme coordinators, NREGS
All the Chief Executive Officers, ZPs and Additional District Programme Coordinators, NREGS.
The Project Officer, ITDA and Additional District Programme Coordinators of Eturu Nagaram (Warangal), Bhadrachalam (Khammam), Utnoor (Adilabad)

Copy to:

The Prl. Secretary, Finance (W&P) Dept., Govt. of Telangana, Hyderabad
The Prl. Secretary, PR., Govt. of Telangana, Hyderabad.
The Prl. Secretary, Irrigation (I&CAD) of Telangana, Hyderabad.
The Prl. Secretary, Tribal Welfare Dept., Govt. of Telangana, Hyderabad
The Secretary, R&B, Govt. of Telangana, Hyderabad

(P.T.O)

-:2:-

The Prl. Secretary, EFS & T Dept., Govt. of Telangana, Hyderabad
The Prl. Chief Conservator of Forests, Govt. of Telangana, Hyderabad
The Commissioner Disaster Management and EO Secy. to Govt.
The Commissioner, AMR-APARD, Rajendranagar, Hyderabad
The Commissioner, Tribal Welfare, Hyderabad
The Chairman and Members of Technical Committee.
The Engineer-in-Chief, Panchayat Raj Dept.
The Engineer-in-Chief, Irrigation Dept.
The Chief Engineer, Tribal Welfare
The Special Officers of NREGS–Telangana Districts
The Secretary, APREG Council, Hyderabad.
The Superintending Engineers of Panchayat Raj of NREGS –Telangana.
The Superintending Engineers of Irrigation Dept., of NREGS –Telangana Districts
PS to Prl. Secretary, RD, Govt. of Telangana, Hyderabad, Hyderabad
PR&RD (Genl) Dept., (2 copies)
SF/SC.

//FORWARDED::BY ORDER//

SECTION OFFICER

ANNEXURE to GO Ms.No. 3 , PR&RD (RD-I) Department, Dated :23-07-2014					
Sl. No.	Category No.	Item of Work	Rates approved in RSSR (GO.Ms.No. 107, PR&RD (RD-II)Dept., dated: 20.03.2013)(in Rs.)	Rates now approved to ensure mini. Wage of Rs.169.0/-(in Rs.)	Remarks
1		Unskilled Labour	149.0/- per day	169.0/ per day	-
2	Bush clearance				
	a	Light shrub	3.70/sqm	4.19/sqm	-
	b	Medium and Dense Shrub /Besharam/ Rubber plants	4.68/sqm	5.30/sqm	-
	c	Thin stemmed Juliflora (stem with periphery upto 150 cms)/ thick shrub	9.29/sqm	10.53/sqm	Thick shrub is relevant in tribal areas only
	d	Thick stemmed Juliflora (stem with periphery more than 150 cms	13.92/sqm	15.78/sqm	-
3	Removal of stumps				
	a	Removal of stumps of girth 30cms to 99cms(small stumps)	96.83/- per each	109.82 per each	-
	b	Removal of stumps of girth 100cms to 199cms(medium stumps)	121.06/- per each	137.3 per each	-
	c	Removal of stumps of girth 200cms to 299 cms(large stumps)	157.36/- per each	178.47 per each	-
	d	Removal of stumps of girth 300cms to 399 cms(large stumps)	205.79/- per each	233.4 per each	-
	e	Removal of stumps of girth 400cms to 499 cms(large stumps)	266.32/- per each	302.06 per each	-
	f	Removal of stumps of girth 500cms to 599 cms(large stumps)	326.83/- per each	370.69 per each	-
4		Removal of water hycinth up to 30cms thick	4.61/Sqm	5.22 /Sqm	-
5		Removal of water hycinth of more than 30cms thick	6.29/Sqm	7.13 /Sqm	-

6

Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in loamy and clayey soils like black cotton soils, red earth and chowdu soils				
Category-I				
a	Contour bunding/Earthen bunding	65.16/ Cum	73.9/ Cum	-
	Breaking of clods, tamping & sectioning for earthen bunding	22.33/ Cum	25.32/ Cum	
b	Terrasing in Hill / slope areas	87.51/ Cum	99.25/ Cum	
c	Land levelling			
d	Conservative furrows			
Category-II				
a	Mini Percolation Tank/Percolation tank	87.51/ Cum	99.25/ Cum	-
b	Recharge of dried up open well			
c	Desilting and Deepening of existing check dams/percolation tanks			
d	Rockfill dams, Gully control works, Loose boulder structure			
e	Check Dam/Check wall			
Category-III				
a	Boundry Trench	120.90/ Cum	137.12/ Cum	-
b	Trench - Cum -Bund			
c	Silo pits			
d	Compost pit			
e	Cattle Proof Trenches			
f	Periphery trench in MI tank			
Category IV				
a	Desilting of Open Well	87.51/ Cum	99.25/ Cum	-
b	Desilting of Drinking Water Tanks/Cattle ponds			
c	Earth work excavation of silt in tank beds (Silt application)			

	Category V					
	a	Formation of approach roads	87.51/ Cum	99.25/ Cum	-	
	b	MI tanks				
	c	Flood Bund				
	d	Filling up of Low Lying and Water Logged Areas in INDIRAMMA Colonies				
	e	New Feeder/Field Channel				
	f	Construction of drains				
	g	Closure of abandoned open wells				
	Category-VI					
	a	Staggered trenches, Continuous Contour trenches	149.0/ Cum	169.0/ Cum	-	
	b	Farm Pond/Dugout pond/Sunken pit				
	c	Water Absorption trench at foot hills				
	d	Digging of new open well				
	Category-VII					
	Plantation pits					
	a	0.9 mtsX0.9 mtsX0.9 mts size pit	126.64/ Cum	143.63/ Cum	-	
	b	0.6 mts X 0.6 mtsX 0.6 mts size of pit				
	c	0.45 mts X 0.45 mtsX 0.45 mts size of pit				
	d	0.3 mts X 0.3 mtsX 0.3 mts size of pit	111.74/ Cum	126.73/ Cum	-	
	7	Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in Hard soils like gravel, moram.,				
Category-I						
a		Contour bunding/Earthen bunding	81.93/ Cum	92.92/ Cum	-	
		Breaking of clods, tamping & sectioning for earthen bunding	26.05/ Cum	29.54/ Cum		
b		Terrasing in Hill / slope areas	108.00/ Cum	122.49/ Cum		
c		Land levelling				
d		Conservative furrows				

Category-II				
a	Mini Percolation Tank/Percolation tank	108.00/ Cum	122.49/ Cum	-
b	Recharge of dried up open well			
c	Desilting and Deepening of existing check dams/percolation tanks			
d	Rockfill dams, Gully control works, Loose boulder structure			
e	Check Dam/Check wall			
Category-III				
a	Boundry Trench	126.64/ Cum	143.63/ Cum	-
b	Trench - Cum -Bund			
c	Silo pits			
d	Compost pit			
e	Cattle Proof Trenches			
f	Periphery trench in MI tank			
Category IV				
a	Formation of approach roads	108.00/ Cum	122.49/ Cum	-
b	MI tanks			
c	Flood Bund			
d	Filling up of Low Lying and Water Logged Areas in INDIRAMMA Colonies			
e	New Feeder/Field Channel			
f	Construction of drains			
g	Closure of abandoned open wells			
Category-V				
a	Staggered trenches, Continuous Contour trenches	167.61/ Cum	190.10/ Cum	-
b	Farm Pond/Dugout pond/Sunken pit			
c	Water Absorption trench at foot hills			
d	Digging of new open well			
Category-VI				
Plantation pits				
a	0.9 mtsX0.9 mtsX0.9 mts size pit	143.40/ Cum	162.64/ Cum	-

	b	0.6 mts X 0.6 mtsX 0.6 mts size of pit				
	c	0.45 mts X 0.45 mtsX 0.45 mts size of pit				
	d	0.3 mts X 0.3 mtsX 0.3 mts size of pit	126.64/ Cum	143.63/ Cum	-	
8	Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in soils with mixture of gravel, pebble and soft disintegrated rock like shales ordinary gravel, stoney earth and earth mixed with fair sized boulders					
	Category-I					
	a	Contour bunding/Earthen bunding	89.38/ Cum	101.37/ Cum	-	
		Breaking of clods, tamping & sectioning for earthen bunding	29.78/ Cum	33.77/ Cum		
	b	Terrasing in Hill / slope areas	119.19/ Cum	135.18/ Cum		
	c	Land levelling				
	d	Conservative furrows				
	Category-II					
	a	Mini Percolation Tank/Percolation tank	119.19/ Cum	135.18/ Cum	-	
	b	Recharge of dried up open well				
	c	Desilting and Deepening of existing check dams/percolation tanks				
	d	Rockfill dams, Gully control works, Loose boulder structure				
	e	Check Dam/Check wall				
	Category-III					
	a	Boundry Trench	134.09/ Cum	152.08/ Cum	-	
	b	Trench - Cum -Bund				
	c	Silo pits				
	d	Compost pit				
	e	Cattle Proof Trenches				
	f	Periphery trench in MI tank				
		Category IV				
		a	Formation of approach	119.19/ Cum	135.18/ Cum	-

		roads			
	b	MI tanks			
	c	Flood Bund			
	d	Filling up of Low Lying and Water Logged Areas in INDIRAMMA Colonies			
	e	New Feeder/Field Channel			
	f	Construction of drains			
	g	Closure of abandoned open wells			
	Category-V				
	a	Staggered trenches, Continuous Contour trenches	163.89/ Cum	185.88/ Cum	-
	b	Farm Pond/Dugout pond/Sunken pit			
	c	Water Absorption trench at foot hills			
	d	Digging of new open well			
	Category-VI				
	Plantation pits				
	a	0.9 mtsX0.9 mtsX0.9 mts size pit	149.00/ Cum	169.00/ Cum	-
	b	0.6 mts X 0.6 mtsX 0.6 mts size of pit			
	c	0.45 mts X 0.45 mtsX 0.45 mts size of pit			
	d	0.3 mts X 0.3 mtsX 0.3 mts size of pit	134.09/ Cum	152.08/ Cum	-
9	Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in soft disintegrated rock soils (removable by pick axes and crow bars)				
	Category-I				
	a	Contour bunding/Earthen bunding	167.61/ Cum	190.10/ Cum	-
		Breaking of clods, tamping & sectioning for earthen bunding			
	b	Terrasing in Hill / slope areas			
	c	Land levelling			
	d	Conservative furrows			
	Category-II				
	a	Mini Percolation	167.61/ Cum	190.10/ Cum	-

		Tank/Percolation tank			
	b	Recharge of dried up open well			
	c	Desilting and Deepening of existing check dams/percolation tanks			
	d	Rockfill dams, Gully control works, Loose boulder structure			
	e	Check Dam/Check wall			
Category-III					
	a	Boundry Trench			
	b	Trench - Cum -Bund			
	c	Silo pits			
	d	Compost pit			
	e	Cattle Proof Trenches			
	f	Periphery trench in MI tank			
			167.61/ Cum	190.10/ Cum	-
Category-IV					
	a	Staggered trenches, Continuous Contour trenches			
	b	Farm Pond/Dugout pond/Sunken pit			
	c	Water Absorption trench at foot hills			
	d	Digging of new open well			
			186.24/ Cum	211.23/ Cum	-
Category V					
	a	Formation of approach roads			
	b	MI tanks			
	c	Flood Bund			
	d	Filling up of Low Lying and Water Logged Areas in INDIRAMMA Colonies			
	e	New Feeder/Field Channel			
	f	Construction of drains			
	g	Closure of abandoned open wells			
			167.61/ Cum	190.10/ Cum	-

10	Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in silt in canals, channels and drains				
	a	Feeder/Field Channel and Irrigation drains upto 1.0 mt depth	65.16/ Cum	73.90/ Cum	-
	b	Renovation of spring channels			
11	Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 2.0 mts in sandy soils or loose soils/wet sand not under water				
	a	Land levelling for land development and Flood control Project	49.24/ Cum	55.84/ Cum	-
12	a	Benching with 0.45mx 0.45m size and 0.60mx0.30m size	22.33/ Rmt	25.32/ Cum	-
13	Carrying of earth / gravel by head loads – Leads & Lifts				
	a	For every additional Lead of 10 mts over and above initial lead of 10mt	18.61/cum	21.10/ Cum	-
	b	For every additional lift of 1mt over and above initial lift of 2mts	18.61/cum	21.10/ Cum	-
14	Conveyance of silt , carted earth, stable casing soil and gravel excluding loading and unloading				
	a	up to 1 km	58.50/-cum	58.50/-cum	No change
	b	2 km	68.25/-cum	68.25/-cum	
	c	3 km	78/-cum	78/-cum	
	d	4km	87.75/-cum	87.75/-cum	
	e	5km	104/-cum	104/-cum	
	f	6km	107/-cum	107/-cum	
	g	7 km	120/-cum	120/-cum	
	h	8 km	132/-cum	132/-cum	
	i	9 km	138/-cum	138/-cum	
	j	10 km	143/-cum	143/-cum	
15		Labour charges for Spreading of silt unloaded by tractor in the field	18.09/- cum	20.51/ Cum	-
16		Labour charges for breaking clods, trimming, sectioning and manual compaction using Dimmisa	18.46/-cum	20.93/ Cum	-
17	Pebble bunding				
	a	Small stone (size more than 40mm) bunding-Labour charges for collecting and putting as bund only.	195.55/ Cum	221.79/ Cum	-

18	Stone revetment (Un skilled)				
	a	Labour charges for revetment for all type of works	325.92/ Cum	369.65/ Cum	-
19	Rough Stone Dry Packing & Stone pitching (Unskilled)				
	a	Rock Fill Dam, Stone Checks & Stone outlets – Labour charges for packing only.	186.24/ Cum	211.23/ Cum	-
	b	Stone Terracing – Labour charges for packing only.	186.24/ Cum	211.23/ Cum	-
20	Plantation works				
	Category : I				
	a	Survey and demarcation	24.19/- per100 nos	27.43/- per100 nos	-
	b	Alignment and fixing of planting point with 0.45 meters length sticks	69.79/-per 100 nos	79.15/- per100 nos	-
	c	0.45 meter sticks preparation and transportation at site.	37.23/- per 100 nos	42.22/- per100 nos	-
	d	i) Internal transportation of bag plants to planting points. (5"x9")	37.23/- per 100 nos	42.22/- per100 nos	-
		ii) Internal transportation of Avenue Plantation. Tall plants	144.52/- per 100 nos	163.91/- per100 nos	-
	e	Refilling of Pits and planting (mxmxm), staking stick			
		i) 0.30 X 0.30 X 0.30 Size pit	0.88/- each	0.99/- each	-
		ii) 0.45 X 0.45 X 0.45 Size pit	2.74/- each	3.10/- each	-
		iii) 0.60 X 0.60 X 0.60 Size pit	5.56/- each	6.30/- each	-
		iv) 0.90 X 0.90 X 0.90 Size pit	8.33/- each	9.44/- each	-
		v) 1.00 X 1.00 X 1.00 Size pit	9.29/- each	10.53/- each	-
	Soil working and weeding				
	Category : I (1 M dia and 0.1 m Depth)				
	a	Avenue Plantation	9.29/- each	10.53/- each	-

	b	Horticulture	9.29/- each	10.53/- each	-
	Category : II (0.5 M dia and 0.1 m Depth)				
	a	Fore shore plantation	2.74/- each	3.10/- each	-
	b	B.H.Afforestation	2.74/- each	3.10/- each	-
	c	Bio Diesel Plantation & Block plantation	2.74/- each	3.10/- each	-
21	Causality Replacement for				
	a	Reopening of Pits for avenue, Horticulture & Blok Plantations.	9.45/- each	10.71/- each	-
	b	Fore share plantation, Barren Hill Afforestation, Bio-Diesel	4.61/- each	5.22/- each	-
22		Watch & Ward and repair to Fence and soil working of each plant including pruning of branches for plantations raised in common property resource lands and lands of SC/ST/assignees.	149.0/- day	169.0/- day	-
23	Bio Fencing / Brush Wood Fencing for barren hill afforestation.				
	a	Nurseries, block plantation and fore shore plantation including collection, transportation and fixing at site	18.60/- Rmt	21.09/- Rmt	-
	b	Avenue Plantation including collection, transportation and fixing at site (Size of 1 m dia and 1.5 m height)	70.46/- each	79.91/- each	-
	c	Horticulture, for lands of SC-ST & Assignee lands only	1862.46/- acre	2112.40/- acre	-
	d	Horticulture fencing 1 st year & 2 nd year maintenance SC-ST& Assignee lands only.	465.60/- acre	528.08/- acre	-
24	Deep Ploughing in				
	a	Fallow Land and Hard Gravel soils (Depth not less than 0.3 meters) using ploughing tractors	1231/- acre	1396/- acre	-
	b	fallow land in ordinary soils using ploughing tractor depth not less than 0.3 m	985/- acre	1117/- acre	-
	c	Cattle cultivator (Double ploughing) in ordinary soils.	740/- acre	839/- acre	-

25		Watering plants of block plantation from the sump constructed (where ever one sump is available per one acre)	2.37/- plant	2.68/- plant	-
26		Watering plants from hand pump/bore well/open well up to distance of 30 mt	3.33/- plant	3.77/- plant	-
27		Watering block plantation from the nearby sources i.e bore well open well or kunta beyond 30 mts distance.	4.15/- plant	4.70/- plant	-
28		Hire charges of tractor mounted water tanker for filling sump	370/- per one trip of 5000 ltrs capacity	420/- per one trip of 5000 ltrs capacity	-
29		Sharpening of crowbar	10/- per day	10/- per day	No change
30		Basket Replenishment charges	3/- per day	3/- per day	No change

J.RAYMOND PETER
PRINCIPAL SECRETARY TO GOVERNMENT (RD)